



# Government of the Cook Islands INFRASTRUCTURE COOK ISLANDS

## Te Tango Angaanga o te Kuki Airani







File Ref: 100.1.3B (11) C16-07

15th September 2016

To Whom It May Concern

Kia Orana,

## RE: <u>Avatiu Valley Bridge Improvements and Stream Embankment Stabilization</u> Project, Contract No C16-07/ID 161710 - Notice to Tenderers No 3 (NTT3)

This Notice To Tenderers (NTT3) serves to advise the following with reference to the above RFT and response to one of the potential tenderers query:

1) The attached revised drawings, sheets 3 and 10 supersedes the current revised drawings. This is also available on the procurement website <a href="https://www.procurement.gov.ck">www.procurement.gov.ck</a>

#### **Explanatory Notes for the Revised Drawings;**

- Sheet 3 additional dimensions made to short retaining walls
- Sheet 10 correction made to dimension from 1200mm to 1800mm

#### Query 1 & 2 from one of the potential tenderers

#### a) Query 1:

On drawing sheet 3 of 10; the length of the toe of spillway is 1800 but under drawings sheet 10 of 10, the toe length is 1200, if "Detail 1" referes to cross-section of spillway then there is a conflict of dimensions. Also, on drawings sheet 3 to 10, the span indicated is 7090, but the outer lines extends beyond the 7090 and connects to the wing wall, so we are assuming that the measurement off the drawing will suffice for the actual outer span.

The same for the southern spillway indicates a 6360 dimension but actually extends to the wing wall, which no longer than 6360.

#### b) Query 2:

On drawing sheet 10 of 10; there is bracing walls, whereas the previous drawing sheet 9 of 9 there is a triangular bracing wall, it is good practice to have bracing walls as this give stability to the structure.

### Response to above Query 1 & 2 below:

- c) Query 1:
  - 1. Total width of splash slab is 1800mm, drawings Sheet 10 will be adjusted and re-issued per attached revised sheet.
  - 2. Length of walls to bridge support walls shown. Length to wing walls to be calculated and included on drawing Sheet 3 and re-issued per revised attached sheet.

- 3. Measurements must not be scaled off the drawings
- d) Query 2:
  - 1. NTT2 specified that new set of drawings is issued, original bracing wall removed.
  - 2. Bracing wall in this case not required stick to the specifications and drawings.
- 3) Please acknowledge by return receipt of this NTT3 by return.

Yours sincerely,

Solomona Solomona

**Contact Officer** 

**INFRASTRUCTURE COOK ISLANDS** 

Malanchar.