



1. Pavement Subgrade CBR to be =5% contractor to confirm on site with scalar Pentrometer testing.
2. Basecourse to comply with specification requirements utility services.
3. Not shown for clarity.